

## Standard Development Timeline

---

*This section is maintained by the drafting team during the development of the standard and will be removed when the standard becomes effective.*

### Development Steps Completed

1. The Standards Committee accepted the Standard Authorization Request (SAR) submitted by the Geomagnetic Disturbance Task Force (GMD TF) and approved Project 2013-03 (Geomagnetic Disturbance Mitigation) on June 5, 2013.
2. The draft standard was posted for a 45-day formal comment period and initial ballot from June 26, 2013 through August 12, 2013. The SAR was posted for informal comment during the same period.
3. The second draft of the standard was posted for a 45-day formal comment period and additional ballot from September 4, 2013 through October 18, 2013.

### Description of Current Draft

This is the third posting of the proposed standard. It is posted for a 10-day final ballot.

Anticipated Actions	Anticipated Date
<del>45-day Formal Comment Period with Ballot</del>	<del>September 2013</del>
Final ballot	October 2013
BOT adoption	November 2013

## Effective Dates

The first day of the first calendar quarter that is six months after the date that this standard is approved by an applicable governmental authority or as otherwise provided for in a jurisdiction where approval by an applicable governmental authority is required for a standard to go into effect. Where approval by an applicable governmental authority is not required, the standard shall become effective on the first day of the first calendar quarter that is six months after the date this standard is adopted by the NERC Board of Trustees or as otherwise provided for in that jurisdiction.

## Version History

Version	Date	Action	Change Tracking
1	TBD	Project 2013-03	N/A

## Definitions of Terms Used in Standard

*This section includes all newly defined or revised terms used in the proposed standard. Terms already defined in the Reliability Standards Glossary of Terms are not repeated here. New or revised definitions listed below become approved when the proposed standard is approved.*

*When the standard becomes effective, these defined terms will be removed from the individual standard and added to the Glossary.*

None

## A. Introduction

1. **Title: Geomagnetic Disturbance Operations**
2. **Number:** EOP-010-1
3. **Purpose:** To mitigate the effects of geomagnetic disturbance (GMD) events by implementing Operating Plans, Processes, and Procedures.
4. **Applicability:**
  - 4.1. **Functional Entities:**
    - 4.1.1 Reliability Coordinator
    - 4.1.2 Transmission Operator with a Transmission Operator Area that includes a power transformer with a high side wye-grounded winding with terminal voltage greater than 200 kV
5. **Background:**

Geomagnetic disturbance (GMD) events have the potential to adversely impact the reliable operation of interconnected transmission systems. During a GMD event, geomagnetically-induced currents (GIC) may cause transformer hot-spot heating or damage, loss of Reactive Power sources, increased Reactive Power demand, and [Protection](#) [System Misoperation](#), the combination of which may result in voltage collapse and blackout.

## B. Requirements and Measures

- R1.** Each Reliability Coordinator shall develop, maintain, and implement a GMD Operating Plan that coordinates GMD Operating Procedures [or Operating Processes](#) within its Reliability Coordinator Area. At a minimum, the GMD Operating Plan shall include: *[Violation Risk Factor: Medium] [Time Horizon: Long-term Planning, Operations Planning, Same-day Operations, Real-time Operations]*

**1.1** A description of activities designed to mitigate the effects of GMD events on the reliable operation of the interconnected transmission system within the Reliability Coordinator Area.

**1.2** A process for the Reliability Coordinator to review the GMD Operating Procedures [or Operating Processes](#) of Transmission Operators ~~within the~~ [its](#) Reliability Coordinator Area.

**Rationale and supporting information for Requirement R1:** An Operating Plan is implemented by carrying out its stated actions.

Coordination is intended to ensure that [Operating Procedures](#) are not in conflict with one another.

An Operating Plan is maintained when it is kept relevant by taking into consideration system configuration, conditions, or operating experience, as needed to accomplish its purpose.

[Elements of Requirement R1 take place in various time horizons. Development of the GMD Operating Plan occurs in the Long-Term Planning Time Horizon. Maintenance of the GMD Operating Plan occurs in the Operations Planning Time Horizon. Implementation of the GMD Operating Plan occurs in the Operations Planning, Same-Day and Real-Time Time Horizons.](#)

**M1.** Each Reliability Coordinator shall have a [current](#) GMD Operating Plan meeting all the provisions of Requirement R1; evidence such as a review or revision history to indicate that the GMD Operating Plan has been maintained; and evidence to show that the plan was implemented as called for in its GMD Operating Plan, such as dated operator logs, voice recordings, or voice transcripts.

**R2.** Each Reliability Coordinator shall disseminate forecasted and current space weather information [as specified to functional entities identified as recipients in](#) ~~in~~ the Reliability Coordinator's GMD Operating Plan. *[Violation Risk Factor: Medium] [Time Horizon: Same-day Operations, Real-time Operations]*

**M2.** Each Reliability Coordinator shall have evidence such as dated operator logs, voice recordings, transcripts, or electronic communications to indicate that forecasted and current space weather information was disseminated as stated in its GMD Operating Plan.

**Rationale and supporting information for Requirement R2:** Requirement R2 replaces IRO-005-3.1a, Requirement R3. IRO-005-4 has been adopted by the NERC Board and filed with FERC, and will retire IRO-005-3.1a Requirement R3. If EOP-010-1 becomes effective prior to the retirement of IRO-005-3.1a, Requirement R2 shall become effective on the first day following retirement of IRO-005-3.1a.

Space weather forecast information can be used for situational awareness and safe posturing of the system. Current space weather information can be used for monitoring progress of a GMD event.

The Reliability Coordinator is responsible for disseminating space weather information to ensure coordination and consistent awareness in its Reliability Coordinator Area.

**R3.** Each Transmission Operator shall develop, maintain, and implement a [GMD](#) Operating Procedure or Operating Process to mitigate the effects of GMD events on the reliable operation of its respective system. At a minimum, the Operating Procedure or Operating Process shall include: *[Violation Risk Factor: Medium] [Time Horizon: Long-term Planning, Operations Planning, Same-day Operations, Real-Time Operations]*

**3.1.** Steps or tasks to receive space weather information.

**3.2.** System Operator actions to be initiated based on predetermined conditions.

**3.3.** The conditions for terminating the Operating Procedure or Operating Process.

**Rationale and supporting information for Requirement R3:**

[In developing an Operating Procedure or Operating Process, an entity may consider entity-specific factors such as geography, geology, and system topology.](#)

An Operating Procedure or Operating Process is maintained when it is kept relevant by taking into consideration system configuration, conditions, or operating experience, as needed to accomplish its purpose.

An Operating Procedure or Operating Process is implemented by carrying out its stated actions.

- M3.** Each Transmission Operator shall have a GMD Operating Procedure or Operating Process meeting all the provisions of Requirement R3; evidence such as a review or revision history to indicate that the GMD Operating Procedure or Operating Process has been maintained; and evidence to show that the Operating Procedure or Operating Process was implemented as called for in its GMD Operating Procedure or Operating Process, such as dated operator logs, voice recordings, or voice transcripts.

## **C. Compliance**

### **1. Compliance Monitoring Process**

#### **1.1. Compliance Enforcement Authority**

As defined in the NERC Rules of Procedure, “Compliance Enforcement Authority” (CEA) means NERC or the Regional Entity in their respective roles of monitoring and enforcing compliance with the NERC Reliability Standards.

#### **1.2. Evidence Retention**

The following evidence retention periods identify the period of time an entity is required to retain specific evidence to demonstrate compliance. For instances where the evidence retention period specified below is shorter than the time since the last audit, the CEA may ask an entity to provide other evidence to show that it was compliant for the full time period since the last audit.

The Reliability Coordinator and Transmission Operator shall keep data or evidence to show compliance as identified below unless directed by its CEA to retain specific evidence for a longer period of time as part of an investigation:

The responsible entities shall retain documentation as evidence for three years.

If a responsible entity is found non-compliant, it shall keep information related to the non-compliance until mitigation is complete and approved or for the time specified above, whichever is longer.

The CEA shall keep the last audit records and all requested and submitted subsequent audit records.

#### **1.3. Compliance Monitoring and Assessment Processes:**

Compliance Audit

Self-Certification

Spot Check

Compliance Investigation

Self-Reporting

Complaint

#### **1.4. Additional Compliance Information**

None

**Table of Compliance Elements**

R #	Time Horizon	VRF	Violation Severity Levels			
			Lower VSL	Moderate VSL	High VSL	Severe VSL
R1	Long-term Planning, Operations Planning, Same-day Operations, Real-time Operations	Medium	The Reliability Coordinator had a GMD Operating Plan, but failed to maintain it.	N/A	The Reliability Coordinator's GMD Operating Plan failed to include one of the required elements as listed in Requirement R1, parts 1.1 or 1.2.	The Reliability Coordinator did not have a GMD Operating Plan OR The Reliability Coordinator failed to implement a GMD Operating Plan within its Reliability Coordinator Area.
R2	Same-day Operations, Real-time Operations	Medium	N/A	N/A	N/A	The Reliability Coordinator failed to disseminate forecasted and current space weather information <u>as specified to all functional entities identified as recipients</u> in the Reliability Coordinator's GMD Operating Plan.
R3	Long-term Planning, Operations	Medium	The Transmission Operator had a GMD Operating Procedure	The Transmission Operator's GMD Operating Procedure	The Transmission Operator's GMD Operating Procedure or	The Transmission Operator did not have a GMD Operating

	<p>Planning, Same-day Operations, Real-time Operations</p>		<p>or Operating Process, but failed to maintain it.</p>	<p>or Operating Process failed to include one of the required elements as listed in Requirement R3, parts 3.1 through 3.3.</p>	<p>Operating Process failed to include two or more of the required elements as listed in Requirement R3, parts 3.1 through 3.3.</p>	<p>Procedure or Operating Process  OR  The Transmission Operator failed to implement its GMD Operating Procedure or Operating Process.</p>
--	--	--	---	--	---	--

**D. Regional Variances**

None.

**E. Interpretations**

None.