

GADS Wind Application Update

February 1, 2020

The following validations and clarifications have been added to the GADS Wind application:

Additional GADS Wind Validation Checks	
Validation/Clarification	Description
Turbine System (MW)	The System Capacity - MW rating of a single turbine in the sub-group. The
	correct Value should be the MW capacity of a single turbine.
	The actual number of physical turbines that exist in the sub-group.
Total Number of Turbines	
	The number of turbines must be greater than zero.
	Gross maximum wind generation that has been generated at continuous
Gross Maximum Potential	full-power operation during performance reporting month.
Production (GMPP)	CAARR (He or 's Marshly V/M subsect Today V/Mar Today
	GMPP = (Hours in Month) X (Number of Turbines) X (Max Turbine
	System Capacity)
Comparison of Gross Maximum	Gross Actual Generation (GAG) must be less than or equal to Gross Max
Potential Production and Gross	Potential Production (GMPP)
Actual Generation (GAG)	The transfer of the design of
	This is equal to the installed capacity less any electrical losses such as
Not Maximum Conscitu (NING)	transformation losses, line losses, and other losses due to transmission between the turbine and the revenue meter.
	between the turbine and the revenue meter.
Net Maximum Capacity (NMC)	Net Maximum Capacity (NMC) may not equal zero when Total Installed
	Capacity (TIC), Gross Actual Generation (GAG) or Net Actual Generation
	(NAG) are greater than zero.
	The number of turbine-hours the sub-group is synchronized to the system.
	It is the turbine-hours that the main contactor is closed and generation is
	provided to the grid.
Contact Turbine Hours (CTH)	
	If reported Contact Turbine Hours (CTH) are equal to zero, then Gross Actual
	Generation (GAG) and Net Actual Generation (NAG) must be equal to zero.
	GAG is the sum of all individual turbine meters before removing station
Cross Astrol Consusting (CAC)	service or auxiliary loads. GAG should be measured as close to the turbine's
	generator as possible so that generation is measured before any auxiliary
Gross Actual Generation (GAG) compared to Net Actual	use by the turbine.
Generation (NAG)	
Generation (NAG)	NAG is the portion of generation delivered by the sub-group to the revenue
	meter. It is possible to have a negative NAG value if the group's station
	service or auxiliary loads are greater than total generation.



Additional GADS Wind Validation Checks	
Validation/Clarification	Description
Gross Actual Generation should not equal Net Actual Generation (due to line losses).	The percentage difference between Gross Actual Generation (GAG) and Net Actual Generation (NAG) should not become greater than 15%.
Contact Turbine Hours	The Contact Turbine Hours (CTH) multiplied by Total Installed Capacity must
Calculations	be greater than or equal to the Gross Actual Generation.
High Cut-Out Wind Speed	The highest wind speed at which the turbine is capable of generating power before cutting out. This can be determined from the turbine operating parameters or the turbine power curve. A wind turbine is designed to produce power over a range of wind speeds. The High Cut Out Wind speed must range from 16.0–35 m/s.
Low Cut-Out Wind Speed	The lowest wind speed that the turbine can continue to generate power before cutting out. This can be determined from the turbine operating parameters or the turbine power curve A wind turbine is designed to produce power over a range of wind speeds.
Cut-In Wind Speed	The Low Cut Out Wind speed must range from 2.0–15.9 m/s. The lowest wind speed that the turbine will start to generate power, in meters per second. This can be determined from the turbine operating parameters or the turbine power curve. The Cut-in wind speeds must range from 0 -15 m/s.
Maximum Operating Temperature	The manufacture minimum operating temperature in degrees Celsius. Maximum Operating Temperature must be within the bounds of 25 to 65° Celsius.
Minimal Operating Temperature	Enter the manufacture maximum operating temperature in degrees Celsius. Minimal Operating Temperature must be within the bounds of -40 to 0° Celsius.

An Addendum has been added to the <u>GADS Wind Data Reporting Instructions</u>.

Document Title 2