# **Standard Development Timeline**

This section is maintained by the drafting team during the development of the standard and will be removed when the standard becomes effective.

#### **Description of Current Draft**

This is the second posting of the draft standard for a 45-day formal comment period with an additional ballot.

Completed Actions	Date
Standards Committee approved SAR for posting	June 10, 2014
SAR posted for comment	July 16, 2014
Standard posted for 45-day comment period and initial ballot	July 30, 2015
Standard posted for a 45-day comment period and successive ballot	November 10, 2016

Anticipated Actions	Date
Final ballot	January – February 2016
NERC Board adoption	February 2016

## New or Modified Terms Used in NERC Reliability Standards

This section includes all new or modified terms used in the proposed standard that will be included in the *Glossary of Terms Used in NERC Reliability Standards* upon applicable regulatory approval. Terms used in the proposed standard that are already defined and are not being modified can be found in the *Glossary of Terms Used in NERC Reliability Standards*. The new or revised terms listed below will be presented for approval with the proposed standard.

Term: None

#### A. Introduction

- 1. Title: Facility Interconnection Requirements
- **2. Number:** FAC-001-3
- **3. Purpose:** To avoid adverse impacts on the reliability of the Bulk Electric System, Transmission Owners and applicable Generator Owners must document and make Facility interconnection requirements available so that entities seeking to interconnect will have the necessary information.

#### 4. Applicability:

#### **4.1. Functional Entities:**

- **4.1.1** Transmission Owner
- **4.1.2** Applicable Generator Owner
  - **4.1.2.1** Generator Owner with a fully executed Agreement to conduct a study on the reliability impact of interconnecting a third party Facility to the Generator Owner's existing Facility that is used to interconnect to the Transmission system.
- 5. Effective Date: See Implementation Plan for FAC-001-3.

#### **B.** Requirements and Measures

- **R1.** Each Transmission Owner shall document Facility interconnection requirements, update them as needed, and make them available upon request. Each Transmission Owner's Facility interconnection requirements shall address interconnection requirements for: [Violation Risk Factor: Lower] [Time Horizon: Long-term Planning]
  - 1.1. generation Facilities;
  - **1.2.** transmission Facilities; and
  - **1.3.** end-user Facilities.
- **M1.** Each Transmission Owner shall have evidence (such as dated, documented Facility interconnection requirements) that it met all requirements in Requirement R1.
- **R2.** Each applicable Generator Owner shall document Facility interconnection requirements and make them available upon request within 45 calendar days of full execution of an Agreement to conduct a study on the reliability impact of interconnecting a third party Facility to the Generator Owner's existing Facility that is used to interconnect to the Transmission system. [Violation Risk Factor: Lower] [Time Horizon: Long-term Planning]
- **M2.** Each applicable Generator Owner shall have evidence (such as dated, documented Facility interconnection requirements) that it met all requirements in Requirement R2.

**Rationale for Requirement R3.3:** Consistent with the Functional Model, there cannot be an assumption that the entity owning the transmission will be the same entity providing the BA function. It is the responsibility of the party interconnecting to make appropriate arrangements with a Balancing Authority to ensure its Facilities are within the BA's metered boundaries, which also serves to facilitate the process of the coordination between the two entities that will be required under numerous other standards upon the start of operation. Under 3.3, the Transmission Owner is responsible for confirming that the party interconnecting has made appropriate provisions with a Balancing Authority to operate within its metered boundaries.

- **R3.** Each Transmission Owner shall address the following items in its Facility interconnection requirements: [Violation Risk Factor: Lower] [Time Horizon: Long-Term Planning]
  - **3.1.** Procedures for coordinated studies of new or materially modified existing interconnections and their impacts on affected system(s).
  - **3.2.** Procedures for notifying those responsible for the reliability of affected system(s) of new or materially modified existing interconnections.
  - **3.3.** Procedures for confirming with those responsible for the reliability of affected systems that new or materially modified Facilities are within a Balancing Authority Area's metered boundaries.
- **M3.** Each Transmission Owner shall have evidence (such as dated, documented Facility interconnection requirements addressing the procedures) that it met all requirements in Requirement R3.

**Rationale for Requirement R4.3:** Consistent with the Functional Model, there cannot be an assumption that the entity owning the generation will be the same entity providing the BA function. It is the responsibility of the party interconnecting to make appropriate arrangements with a Balancing Authority to ensure its Facilities are within the BA's metered boundaries, which also serves to facilitate the process of the coordination between the two entities that will be required under numerous other standards upon the start of operation. Under 4.3, the Generator Owner is responsible for confirming that the party interconnecting has made appropriate provisions with a Balancing Authority to operate within its metered boundaries.

- **R4.** Each applicable Generator Owner shall address the following items in its Facility interconnection requirements: [Violation Risk Factor: Lower] [Time Horizon: Long-Term Planning]
  - **4.1.** Procedures for coordinated studies of new interconnections and their impacts on affected system(s).

- **4.2.** Procedures for notifying those responsible for the reliability of affected system(s) of new interconnections.
- **4.3.** Procedures for confirming with those responsible for the reliability of affected systems that new or materially modified Facilities are within a Balancing Authority Area's metered boundaries.
- **M4.** Each applicable Generator Owner shall have evidence (such as dated, documented Facility interconnection requirements addressing the procedures) that it met all requirements in Requirement R4.

### C. Compliance

#### 1. Compliance Monitoring Process

#### **1.1. Compliance Enforcement Authority**

As defined in the NERC Rules of Procedure, "Compliance Enforcement Authority" (CEA) means NERC or the Regional Entity in their respective roles of monitoring and enforcing compliance with the NERC Reliability Standards.

#### **1.2. Evidence Retention**

The following evidence retention periods identify the period of time an entity is required to retain specific evidence to demonstrate compliance. For instances where the evidence retention period specified below is shorter than the time since the last audit, the CEA may ask an entity to provide other evidence to show that it was compliant for the full time period since the last audit.

The applicable Functional Entity shall keep data or evidence to show compliance as identified below unless directed by its CEA to retain specific evidence for a longer period of time as part of an investigation:

The responsible entities shall retain documentation as evidence for three years.

If a responsible entity is found non-compliant, it shall keep information related to the non-compliance until mitigation is complete and approved or for the time specified above, whichever is longer.

The CEA shall keep the last audit records and all requested and submitted subsequent audit records.

#### **1.3.** Compliance Monitoring and Assessment Processes:

Compliance Audit Self-Certification Spot Check Compliance Investigation Self-Reporting Complaint

## **1.4.** Additional Compliance Information

None

# Table of Compliance Elements

R #	Time Horizon	VRF	Violation Severity Levels			
	1012011		Lower VSL	Moderate VSL	High VSL	Severe VSL
R1	Long-term Planning	Long-term Planning Lower N/A N/A N/A N/A N/A N/A N/A N/A N/A N/A	The Transmission Owner documented Facility interconnection requirements, but failed to update them as needed and failed to make them available upon request.	The Transmission Owner did not document Facility interconnection requirements.		
				OR The Transmission Owner documented Facility interconnection requirements and made them available upon request, but failed to update them as needed. OR The Transmission Owner documented Facility interconnection requirements, updated them as needed, and made them available upon request, but	OR The Transmission Owner documented Facility interconnection requirements, updated them as needed, and made them available upon request, but failed to address interconnection requirements for two of the Facilities as specified in R1, Parts 1.1, 1.2, or 1.3.	

				failed to address interconnection requirements for one of the Facilities as specified in R1, Parts 1.1, 1.2, or 1.3.		
R2	Long-term Planning	Lower	The applicable Generator Owner failed to document Facility interconnection requirements and make them available upon request until more than 45 calendar days but less than or equal to 60 calendar days after full execution of an Agreement to conduct a study on the reliability impact of interconnecting a third party Facility to the Generator Owner's existing Facility that is used to interconnect to the Transmission system.	The applicable Generator Owner failed to document Facility interconnection requirements and make them available upon request until more than 60 calendar days but less than or equal to 70 calendar days after full execution of an Agreement to conduct a study on the reliability impact of interconnecting a third party Facility to the Generator Owner's existing Facility that is used to interconnect to the Transmission system.	The applicable Generator Owner failed to document Facility interconnection requirements and make them available upon request until more than 70 calendar days but less than or equal to 80 calendar days after full execution of an Agreement to conduct a study on the reliability impact of interconnecting a third party Facility to the Generator Owner's existing Facility that is used to interconnect to the Transmission system.	The applicable Generator Owner failed to document Facility interconnection requirements and make them available upon request until more than 80 calendar days after full execution of an Agreement to conduct a study on the reliability impact of interconnecting a third party Facility to the Generator Owner's existing Facility that is used to interconnect to the Transmission system.

R3	Long-term Planning	Lower	N/A	The Transmission Owner failed to address one part of Requirement R3 Part 3.1 through Part 3.3.	The Transmission Owner failed to address two parts of Requirement R3 Part 3.1 through Part 3.3.	The Transmission Owner failed to address Requirement R3 Part 3.1 through Part 3.3.
R4	Long-term Planning	Lower	N/A	The Generator Owner failed to address one part of Requirement R4 Part 4.1 through Part 4.3.	The Generator Owner failed to address two parts of Requirement R4 Part 4.1 through Part 4.3.	The Generator Owner failed to address Requirement R4 Part 4.1 through Part 4.3.

## **D.** Regional Variances

None.

## **E.** Interpretations

None.

## F. Associated Documents

None.

## **Guidelines and Technical Basis**

Entities should have documentation to support the technical rationale for determining whether an existing interconnection was "materially modified." Recognizing that what constitutes a "material modification" will vary from entity to entity, the intent is for this determination to be based on engineering judgment.

#### **Requirement R3:**

Originally the Parts of R3, with the exception of the first two bullets, which were added by the Project 2010-02 drafting team, this list has been moved to the Guidelines and Technical Basis section to provide entities with the flexibility to determine the Facility interconnection requirements that are technically appropriate for their respective Facilities. Including them as Parts of R3 was deemed too prescriptive, as frequently some items in the list do not apply to all applicable entities – and some applicable entities will have requirements that are not included in this list.

Each Transmission Owner and applicable Generator Owner should consider the following items in the development of Facility interconnection requirements:

- Procedures for requesting a new Facility interconnection or material modification to an existing interconnection
- Data required to properly study the interconnection
- Voltage level and MW and MVAR capacity or demand at the point of interconnection
- Breaker duty and surge protection
- System protection and coordination
- Metering and telecommunications
- Grounding and safety issues
- Insulation and insulation coordination
- Voltage, Reactive Power (including specifications for minimum static and dynamic reactive power requirements), and power factor control
- Power quality impacts
- Equipment ratings
- Synchronizing of Facilities
- Maintenance coordination
- Operational issues (abnormal frequency and voltages)
- Inspection requirements for new or materially modified existing interconnections
- Communications and procedures during normal and emergency operating conditions

# **Version History**

Version	Date	Date Action	
0	April 1, 2005	Effective Date	New
1		Added requirements for Generator Owner and brought overall standard format up to date.	Revision under Project 2010-07
1	February 9, 2012	Adopted by the Board of Trustees	
1	September 19, 2013	A FERC order was issued on September 19, 2013, approving FAC-001-1. This standard became enforceable on November 25, 2013 for Transmission Owners. For Generator Owners, the standard becomes enforceable on January 1, 2015.	
2		Revisions to implement the recommendations of the FAC Five- Year Review Team.	Revision under Project 2010-02
2	August 14, 2014	Adopted by the Board of Trustees	
2	November 6, 2014	FERC letter order issued approving FAC-001-2.	